MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE INSPECTOR-GENERAL OF EDUCATION IN MYSORE, BANGALORE.

Notification dated 15th April 1925.

Notice is hereby given that sealed tenders will be received at the office of the Inspector-General of Education in Mysore, Bangalore, up to 4th May 1925, for the construction of a building for the Girls' School at Hosdurga, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1925.

2. The plans, detailed estimate and conditions may be seen at the office of the Inspector-General of Education between the hours of 12 Noon and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Inspector-General of Education. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a receipt for having deposited a sum of Rs. 50 in the State or other Government Treasuries in cash or Government Promissory Notes, as earnest money, and be superscribed 'Tenders for construction of a building for the Girls' School at Hosdurga' in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Inspector-General of Education in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, providing for a deposit of 5 per cent of the estimated cost of the work; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the office of the Inspector-General of Education in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate.

No.	Details of work	Per	Quantity
1	Earthwork excavation	C.yd.	34
2	Filling foundation and basement with burnt stone in mud ..	C.ft.	1,411
3	Superstructure: burnt brick in mud	,,	2,001
4	Burnt stone slabs roughly dressed	S.ft.	182
5	Burnt brick in chunnam pillars 1½' x 1½' x 10' with cornice at top and bottom plastering, complete.	No.	6
6	Honney wood work wrought and put up	C.ft.	91·36
7	Roofing with first class Mangalore tiles on teak reepers 2" x 1", complete ..	Sqr	18·12
8	Ridge tiles set in mortar	R.ft.	88
9	Zinc sheets for valleys with teak plank 1" x 3' with chunnam border plaster, complete.	,,	16
10	Chunnam plastering	Sqr.	35·70
11	White and colour washing two coats	,,	35·70
12	Coping over compound wall 1½' x 9" with plaster, complete	R.ft.	52
13	Chunnam borders over roof	,,	42
14	Teakwood battened doors with hinges, bolts, etc., complete	S.ft.	46
15	Teakwood battened windows with iron bars, hooks, etc., complete	,,	41
16	Chocolate painting two coats	Sqr.	2·26
17	Wood oiling to wood work	,,	16·00
18	Chunnam pointing to basement	,,	4·07
19	Clearing site and levelling ground and unforeseen items	Lump sum	..

K. RANGASWAMY IYENGAR,
For Inspector-General of Education.

6 D